

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20138-00-00  
Spot: NWSW Sec/Twnshp/Rge: 2-1S-34W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: CHLEBORAD Well #: 4  
County: RAWLINS Total Vertical Depth: 4250 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

PROD Size: 5.5 feet: 4248 w/150 sxs cmt  
SURF Size: 8.625 feet: 289 w/225 sxs cmt

4138<sup>13</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/11/2004 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 300 sxs Midcon II cement and 1000# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/11/2004 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

TD 4250'. PBTD 4240'. TOC at 3528'. Casing squeezed from 2950' - 3000'.  
Junk in hole at 3248'. Holes in 5 1/2" production pipe.  
8 5/8" surface casing set at 289' w/225 sxs cement. 5 1/2" production casing set at 4248' w/150 sxs cement.  
Ran tubing to 2400' - pumped 120 sxs cement with 600# hulls.  
Pulled tubing to 1200' - pumped 85 sxs cement with 400# hulls.  
Pulled tubing to 600' - pumped 40 sxs cement. Cement to surface. Pulled tubing to surface.  
Connected to 5 1/2" production casing - pumped 10 sxs cement.  
Max. P.S.I. 200#. S.I.P. 200#.  
Connected to 8 5/8" surface pipe - pumped 30 sxs cement.  
Max. P.S.I. 125#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3996	4191		

RECEIVED  
MAY 25 2004  
KCC WICHITA

Remarks: LEASE RENAMED CAHOJ UNIT 2-4. SWIFT SERAVICES, INC.-TICKET #6760.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

5-25-04

NOV. NO.


2004061601

MAY 19 2004

131011  
 0000

131011

THOS. H. ALLAN #4 CHLEBORAD 2-1-34W  
 WICHITA, KANSAS C NW SW  
 CONTR MURFIN DRILLING CO. CTY RAWLINS  
 GEOL BERNARD LOUNSBURY FIELD CAHOJ NE  
 E 3087 RB CM 6/15/72 <sup>CARD</sup> ISSUED 7/27/72 IP P 80 BOPD N/W  
 LKC 4092-96  
 API 15-153-20, 138 GR 35



LOG	TOPS	DEPTH	DATUM
ANHY		2942	+ 145
B ANHY		2977	+ 110
WAB		3588	- 501
TOP		3801	- 714
DEER CR		3836	- 749
OREAD		3891	- 804
B OREAD		3950	- 863
DOUG SD		3955	- 868
LKC		3994	- 907
LTD		4248	-1161
RTD		4250	-1163

8 5/8" 289/225sx; 5 1/2" 4248/150sx  
 DST(1) 3998-4076/30-30-30-30, 60'M,  
 BHP 1140-1053#, FP 54-81#  
 DST(2) 4075-4106/30-30-90-45, 720'GIP,  
 180'CO, 180'O&GCM, BHP 820-820#,  
 FP 33-163#  
 MICT, PF 4092-4096, A250MA + 1500 REG,  
 SWBG LD, POP.

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS