

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20388-00-00
Spot: SWNESE Sec/Twnshp/Rge: 29-9S-24W
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: HOETING UNIT Well #: 2-3
County: GRAHAM Total Vertical Depth: 4160 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 4.5 feet: 4137 225 SX CMT
SURF Size: 8.625 feet: 262 190 SX CMT

135²⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/12/2004 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered out 275 sxs Swift Multi Density Cement - 500# hulls.
No squeeze records. Perf Anhy at 2250'. Dakota at 1100'.
Top of fish 3879'. Left 6 joints tubing with anchor catcher in hole.
Squeezed at 3074' - 3200' with 100 sxs in 1997.
Fluid level at 1600'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2004 11:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated Anhy at 2250' and Dakota at 1100'.
Ran tubing to 2316'.
Swift Services pumped 10 sxs SMD, followed with 75 sxs SMD with 350# hulls.
Pulled tubing to 1219'.
Swift pumped 70 sxs SMD with 150# hulls - cement circulated.
PTOH. Squeezed with 10 sxs.
Max. P.S.I. 500#. S.I.P. 500#.
Hooked up to backside. Swift pumped 15 sxs.
Blew hole in 8 5/8" one foot below head.
8 5/8" full of cement.

Perfs:

Top	Bot	Thru	Comments
4084	4088		
4066	4072		
4048	4052		
4027	4031		
3934	3938		
3916	3920		

RECEIVED
MAY 25 2004
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS GEORGE NICKELSON #3. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 5.25.04

INV. NO. 2004061601

Form CP-2/3

MAY 19 2004

Aka Hoeting 2-3


DON E. PRATT #3 GEO. NICKELSON 29-9-24W
HAYS, KANSAS SW NE SE
CONTR L. J. DREILING & SONS CTY GRAHAM

GEOL J. R. GREEN FIELD HOETING

E 2554 KB CM 10/24/70 CARD ISSUED 1/14/71 IP P 80 BOPD N/W

API 15-065-20,388

LKC 4027-88
GR 39.6



WELEX	TOPS	DEPTH	DATUM	
TOP		3634	-1080	8 5/8" 262/190SX; 5 1/2" 4143/225SX
HEEB		3850	-1296	DST(1) 3882-3960/1', 1400' MSW, BHP 927-927#/30", FP 143-678#
TOR		3874	-1320	DST(2) 3958-4000/2', 400' MSW, BHP 882-758#/30", FP 27-223#
LKC		3886	-1332	DST(3) 4014-4060/2', 30' HOCM, FBHP 455# FP 26-66#
BKC		4117	-1563	DST(4) 4054-4100/1', 1890' GIP, 598' CGO, BHP 856-847#, FP 36-250#
LID		4160	-1606	

MICT, COTD, PF 16/4084-88, 4066-72,
4048-52, 4027-31 SWB DRY GSG & O SD/12
FU 900' FL (APPX 150' FILT WTR) RAN PKRS
(BTM PERFS COMM) RESET PKRS (J) A1500A750
(H & I ZN) PULL PKRS & TBG SD/12 FU
2200' SWB LD SWB 2HRS 40BOPH 1100' OB,
POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

1WAO16EF

Vertical text on the left margin, possibly a stamp or reference code.