

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-00131-00-01  
Spot: NENW Sec/Twnshp/Rge: 6-15S-29W  
4620 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: COBERLY OWWO Well #: 2  
County: GOVE Total Vertical Depth: 4350 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

PROD Size: 5.5 feet: 4349 w/200 sxs cmt  
SURF Size: 8.625 feet: 104 w/100 sxs cmt

4141 38

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/10/2004 1:00 PM

Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (316) 772-8649

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Fluid level 900'.  
No squeeze records. Perf anhy at 2075'. Dakota at 1058'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/10/2004 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated at 2075' and 1050'.  
Ran tubing to 4200'.  
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 200# hulls.  
Pulled tubing to 2300'.  
Allied pumped 175 sxs cement with 300# hulls.  
Pulled tubing to 900'.  
Allied pumped 65 sxs cwc. PTOH.  
Topped off with 20 sxs cement. Hole full.  
Hooked up to backside.  
Allied pumped 25 sxs cement - 300# - blew packing out.

Perfs:

Top	Bot	Thru	Comments
3739	4194		

RECEIVED  
MAY 25 2004  
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS COBERLY #1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 5.25.04  
INV. NO. 2004061600


Form CP-2/3

MAY 19 2004

OKMAR OIL CO. #2 COBERLY "OWWO"  
 970 4TH FINANCIAL CENTER, WICHITA, KS.  
 CONTR SIRATA DRLG. CO. CTY GOVE

6-15-29W  
 C NE NW

GEOL \_\_\_\_\_ FIELD LUNGGREN EXT (1/4)  
 E 2659 KB CM 1/13/76 <sup>CARD</sup> ISSUED 5/6/76 IP P 2 BOPO + 6 BWPD  
 LKC 3739-57 OA



SMP	TOPS	DEPTH	DATUM	
ANH		2058	+ 501	OLD INFO: OPERATOR WAS WYCOFF BROS. #1
B ANH		2090	+ 569	ROSCOE COBERLY; SPD 12/16/63, SET 8" @
HEEB		3657	- 998	104/95SX; COMPLETED AS D&A/MISS SPERG
TOP		3675	-1016	1/9/64
LANS		3693	-1034	DST (1) 4282-4300/70", REC 50'M, SIP
BKC		4014	-1325	1060-900#, FP 0-0#
MARM		4045	-1386	DST (2) 4322-50/2', REC 160'M, SIP
PAW		4140	-1481	1190-1070#, FP 90-100#
FT SC		4206	-1547	
CHER SH		4231	-1572	NEW INFO: RE-ENTERED 1/13/76, SET 5 1/2
CONG		4303	-1644	4349/200SX,
MISS ST L		4318	-1659	MICT - CO, PF (LKC B) 3739-42, (LKC C)
MISS SPERG		4327	-1668	3752-57 SWB DWN + SWB AVER 2.73 BFPH
RTD		4350	-1691	(67% O)/7HRS, AC 1500 SWB DWN + SWB 5.2
				BFPH, (22% O)/2HRS, ONFU 2600' FL (225' O)
				RT + R, POP, PMP LD, P EST 2 BOPO + 6
				BWPD

INDEPENDENT OIL & GAS SERVICE

WACOICEP

FMS