

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20600-00-00
Spot: SESESESE Sec/Twnshp/Rge: 3-1S-34W
100 feet from S Section Line, 100 feet from E Section Line
Lease Name: CAHOJ NE B Well #: 2-W
County: RAWLINS Total Vertical Depth: 4290 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PKR Size: feet: 4093
PROD Size: 5.5 feet: 4289 w/480 sxs cmt
SURF Size: 8.625 feet: 304 w/240 sxs cmt
T1 Size: 1.5 feet: 4093

139⁴³

Well Type: EOR UIC Docket No: E23976.2 Date/Time to Plug: 05/18/2004 10:15 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 300 sxs Midcon II cement and 750# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2004 12:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 304' w/240 sxs cement. 5 1/2" production casing set at 4289' w/480 sxs cement.
DV Tool at 2954' w/390 sxs cement. PBTD 4249'.
Junk in hole from 2314' - 3879'. Packer at 3879'.
Ran tubing to 2100' - pumped 125 sxs cement with 450# hulls. Cement to surface.
Pulled tubing to 1000' - pumped 15 sxs cement with 50# hulls. Pulled tubing to surface.
Connected to 5 1/2" production casing - pumped 5 sxs cement.
Max. P.S.I. 450#. S.I.P. 450#.
Connected to 8 5/8" surface pipe - pumped 5 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
4182	4184		
4175	4177		
4132	4136		
4082	4087		
4057	4059		
4034	4036		
3984	3987		

RECEIVED
MAY 25 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)


INVOICED

DATE 5-25-04
INV. NO. 2004061601

Form CP-2/3

MAY 19 2004

MURFIN DRILLING COMPANY
 250 N. WATER, #300 WICHITA, KS. 67202
 CONTR COMPANY TOOLS
 GEOL ROGER WELTY
 #2-W 'B' CAHOJ NE
 3-1-34W
 100' FSL & 100' FEL, SE/4
 CTY RAWLINS
 FIELD CAHOJ
 ELV 3091 KB SPD 4/29/85 CARD ISSUED 7/25/85 IP WIW
 3086 GL DRLG COMP 5/5/85 LKC 4175-4184 OA



LOG	Tops	Depth/Datum	API 15-153-20,600
ANH	2935+	156	8 5/8 " 304 / 240SX, 5 1/2 " 4289 / 480SX, MULTI STAGE COL- LAR 2954 / 390SX NO CORES OR DST'S MICT - CO, PF (LKC) 4182-84 & 4175-77, W / 4 SPF, AC 250G (MOD-202), SWB DWN, NON-COMMERCIAL, SET 1 1/2 " TBG AT 4093', WIW - INJECTION RATE SATISFACTORY
B/ANH	2970+	121	
TOP	3785-	694	
OREAD	3878-	787	
LANS	3980-	889	
BKC	4238-	1147	
PBTD	4249-	1158	
RTD	4290-	1199	

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

INVOICE