

6031406

API NUMBER 15-153-30090-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

150 N. C. NE NE SEC. 20, T 1 S, R 34 W&E

5100 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

*Cahoj Unit 56

Lease Name Cahoj G Well # 1

Operator: Rama Operating Co. Inc.

County Rawlins 143.65

Name & Address Box 159

Well Total Depth 4420 feet

Stafford, Ks. 67578

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address _____

Company to plug at: Hour: PM Day: 21 Month: August Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) _____

were: 8 5/8 set at 371 w/300 sks cwc. 5 1/2 casing set at 4415 w/200 sks.

PBTD 4383. Order 300 sks 65/35 poz 8% gel 500 lbs. hulls. Allied Cement Co.

Large water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:20PM Day: 21 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Mix and pump through tubing 250 sks cement blend w/500 lbs.

hulls mixed in to circulate cement to surface. Also, circulated cement up backside from

deep. Closed in backside laid down tubing. Sq 5 1/2 and annulus w/total of 290 sks cement blend

to max psi 300 lbs. Close in psi 150 lb.s Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1990
10-03-90
CONSERVATION DIVISION

Remarks: _____

(If additional description is necessary, use BACK of this form.) Kansas

INVOICED (do not observe this plugging.)

DATE 10-8-90

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

INV. NO. 29564