

15-153-00087-00-00

6 031433

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
C E/2 W/2 SE. 18, T 1, S, R 34 W/E<sup>xx</sup>

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911  
Operator: Rama Operating Co. Inc.  
Name & Address: Box 159, Stafford, Ks. 67578

1320 feet from S section line  
1650 feet from E section line  
Lease Name Cahoj B Well # 3 #49  
County Rawlins 141.37  
Well Total Depth 4350 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 372

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number  
Address Russell, Ks.

Company to plug at: Hour: PM Day: 11 Month: Sept Year: 19 90

Plugging proposal received from Lloyd  
(company name) Rama (phone)

were: 8 5/8 set at 372 w/300 sks cwc 5 1/2 set at 4350 w/250 sks.  
Perf 4050 - 4272. Order 300 sks 65/35 poz 10% gel 500 lbs. hulls.  
Allied Cement Co. Larue water truck. Perf at 2245; Kiowa hole open to production.  
perfs: low fluid level.

Plugging Proposal Received by Carl (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour 4:50 PM Day: 11 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sq annulus w/30 sks cement blend psi locked up, blew out head. Sq 5 1/2 w/75 sks straight cement blend followed w/205 sks cement blend w/500 lbs. hulls mixed into max psi 500 lbs. Close in psi 150 lbs. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

OCT 3 1990 10-3-90 CONSERVATION DIVISION WICHITA, KANSAS

Remarks: Anhy 3031-3052+ - Elev. not shot due to depth and water quality  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-8-90  
INV. NO. 29572

*John S.*

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow