

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20077-00-00
Spot: NWNE Sec/Twnshp/Rge: 18-1S-34W
660 feet from N Section Line, 1980 feet from E Section Line
Lease/Unit Name: A SRAMEK Well Number: 1
County: RAWLINS Total Vertical Depth: 4299 feet

Operator License No.: 3602
Op Name: PHILPOTT OIL & GAS CO INC
Address: PO BOX 450 408 MAIN
ATWOOD, KS 67730

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 256
Production: Size 5.5 feet: 4299
Liner: Size _____ feet:

\$139.72

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/02/2001 8:00 AM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 9 yards Redi-Mix - 6 sxs common with sand/yard.

Plugging Proposal Received By: CARL GOODROW
Date/Time Plugging Completed: 05/02/2001 10:00 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 256' w/225 sxs cwc. 5 1/2" set at 4299' w/200 sxs.
PBSD 4266'. Prod. Perfs 4115' - 4214'.
Three shots recovered 1600' of 5 1/2" casing.
Fluid level low in hole.
Filled hole with 9 yards Redi-Mix. (11 yards by yield).
This well is in the exempt area for ALT. II.

INVOICED

DATE 5-29-01
INV. NO. 2001061838

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 22 2001
5-22-2001
CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

MD

Signed

Carl Goodrow

(TECHNICIAN)

MAY 10 2001

