

4060240

8-26  
API NUMBER 15- 153-20,781-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SW, SEC. 19, T 1 S, R 34 W/EX  
660 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30700

Lease Name Leo Well # 1

Operator: Abraxas Production Corp.

County Rawlins

Name & Address P.O. Box 17485

Well Total Depth 4380 142.35 feet

San Antonio, TX 78217

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 30606

Address Wichita, KS

Company to plug at: Hour: 6:45AM Day: 26 Month: August Year: 19 91

Plugging proposal received from Keith VanPelt

(company name) Murfin Drilling Co. (phone)

were: Order 190 sxs. 60/40pos 6%gel 1/4# floccel per sx.

Space all plugs with heavy drilling mud through drill pipe

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 05 1991  
9-5-91  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XXXXXX

Operations Completed: Hour: 6:45AM Day: 26 Month: August Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3075' with 25 sxs. Anhydrite 3054-3093'

2nd plug at 2300' with 100 sxs. Dakota 1992-2292'

3rd plug at 360' with 40 sxs. Surface pipe to 307'

4th plug at 40' with 10 sxs.

rathole with 15 sxs.

Remarks: Halliburton Cementing  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-13-91

INV. NO. 33120

8-26

Herb S

Signed   
(TECHNICIAN)

Herb Deines