

4-7
4-041362

112 R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,787 ⁰⁰⁻⁰⁰
S2 SW NE /4 SEC. 16, 01 S, 35 W
2970 feet from S section line
1980 feet from E section line

Operator license# 6875

Lease Berdean well # 1

Operator: Marmik Oil Company

County Rawlins

Address: 200 N. Jefferson #500
El Dorado, AR 71730
501-862-8546

Well total depth 4550 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 296 feet
w/205 sx.

147.87

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Halliburton Cementing License#

Address: Oberlin, Kansas

Company to plug at: Hour: 12:30P.M Day: 7 Month: April Year: 92

Plugging proposal received from: Harold Maley

Company: Halliburton/Abercrombie Phone:

Were: Order 255 sx. cement - 60/40 pozmix - 6% gel. - 1/4 # sx. flocele. Heavy mud between all plugs. Pump cement down drill pipe. Anhydrite 3076' - 3114'. Dakota 2330'.

RECEIVED
KANSAS CORPORATION COMMISSION

APR 20 1992
420-92

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:15P.M., Day: 7, Month: April, Year: 92

Actual plugging report: Note: Lost circulation during Dakota plug placement. Waited 6 hrs. Tagged top of hard cement at 2062' and spotted 65 sx. additional cement at lost circulation zone.
25 sx. @ 3100'.
100 sx. @ 2330'.
65 sx. @ 2062'.
40 sx. @ 325'.
10 sx. @ 40'.
15 sx. in Rathole.

Remarks: Lost circulation @ 2168' and 2364' while drilling.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did not [X] observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE 4-27-92

INV. NO. 35067

HO