

6 070267

API NUMBER 15-153-20, 582-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1610 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8389

Lease Name SEGNE Well # 21-1

Operator: GREENWOOD RESOURCES INC.
Name & Address: 315 INVERNESS WAY SOUTH.
ENGLEWOOD, COLORADO
80112

County RHOLLINS 144.79
Well Total Depth 4455 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A 4

Other well as hereinafter indicated _____ 196 #190

Plugging Contractor FIBERCROMBIE DRILLING INC. License Number _____

Address WICHITA, KANSAS, 67202

Company to plug at: Hour: 3:10 PM Day: 4th Month: DEC Year: 19 84

Plugging proposal received from WALLY TOWNS.

(company name) FIBERCROMBIE DRILLING INC. (phone) 303-790-1266

were: 8 5/8" - 304 FT SP. CUL #1/270^{SK 60%} 30% 20% 1/40 Pozmix CA-CL - GEL - (BY SUN CNT)
ORDER 220^{SK 50%} 1/50 Pozmix GEL - CA-CL - 1^{SK 70%} CELE - AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS
NO ARDUCKLE - KC WELL - NO CIRCULATION PROBLEMS, MUD VIS. 50 Weight 9.4
EV. 3221 - ANH 3101 - ASKED OPERATOR TO LOWER SUCTION BEFORE HE

RECONDITIONS HOLE Plugging Proposal Received by Marion Schmidt

Plugging Operations attended by Agent?: None Part _____ None
Operations Completed: Hour 2:45 AM Day: 5th Month: DEC Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 220^{SK 50%} 1/50 Pozmix GEL - CA-CL - 1^{SK 70%} CELE - 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS
1st PLUG @ 3120 FT #1/30^{SK} CNT, 2nd PLUG @ 2070 FT #1/100 CNT & CELE.
3rd PLUG @ 330 FT #1/60^{SK} CNT, 4th PLUG ^{30% 10% BRIDGE} HULLS - PLUG @ 40 FT #1/10^{SK} CNT
10th IN RAT HOLE (CIRCULATE) CEMENTED BY SUN CNT

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I / did not observe this plugging.

DATE 12-18-84

INV. NO. 6001

Signed Marion Schmidt
(TECHNICIAN) BOIC 36-7-84
12-18-84

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

COLLECTORIAL
CARD MUST BE SIGNED
11-29-84

Starting Date 11-28-84
month day year

API Number 15- 153-20,582 (Amended)
00-002

OPERATOR License # 8389
GREENWOOD RESOURCES, INC.

S.W. N.W. Sec. 21, Twp. 1 S, Rgn. 35. East West
(Location)

Address 305 Inverness Way South
City/State/Zip Englewood, CO 80112

* ...1610... Ft North from Southeast Corner of Section
...4950... Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

Contact Person Poul Poulsen
Phone 303/790-1266

CONTRACTOR License # Not Available
Name Abercrombie
City/State Wichita, KS

Nearest lease or unit boundary line 330 feet
County Rawlins
Lease Name Segne Well# 21-1

Well Drilled For Well Class: Type Equipment:
 Oil Infield Mud Rotary
 Gas Pool Est. Air Rotary
 OWWO Expl. Wildcat Cable

RECEIVED
STATE CORPORATION COMMISSION

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:

DEC 1 0 1984

Depth to Bottom of fresh water 250' feet
Lowest usable water formation Unconsolidated

Operator
Well Name
Comp Date
Old Total Depth 4500' feet

CONSERVATION DIVISION
Wichita, Kansas

Depth to Bottom of usable water 300' feet
Surface pipe by Alternate: 2
Surface pipe to be set 350' feet

Projected Total Depth
Projected Formation at TD Lansing/Kansas City
Expected Producing Formations Lansing

Conductor pipe if any required
Ground surface elevation N/A feet MSL
This Authorization Expires 4-18-85

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Approved By [Signature] 11-29-84
WAS SWSW NE
1970 FSL

Date 11-26-84 Signature of Operator or Agent

[Signature: Paul E. Poulsen]

Title V.P. Engineering
Form CP-16