

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

15-073-19337.00.01

API NUMBER 5-31-46

LEASE NAME Sullivan

WELL NUMBER W-25

1471
1650 Ft. from S Section Line

3045
2976 Ft. from E Section Line

SEC. 14 TWP. 24 RGE. 12 (E) or (W)

COUNTY Greenwood

Date Well Completed 5-31-46

Plugging Commenced 10-28-03

Plugging Completed 10-31-03

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R.R. Abderhalden

ADDRESS 100 S. Main, Suite 510, Wichita, Kansas 67202

PHONE/(316) 262-3411 OPERATORS LICENSE NO. 5394

Character of Well Input EOR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-27-03 (date)

by Mike Heffern (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Mississippi Depth to Top 1800 Bottom 1812 T.D. 1813

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out	RECEIVED
<u>Prod</u>			<u>1781</u>	<u>6 5/8</u>	<u>1781</u>		<u>146</u> KANSAS CORPORATION COMMISSION
<u>Surf</u>			<u>24</u>	<u>8-6.25</u>	<u>24</u>	<u>0</u>	<u>NOV 04 2003</u>
							<u>11-04-2003</u>
							CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the plug fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Shot casing @ 864. Ran tubing to 878 feet and pumped 60 sack cement. Shot casing @ 146 feet and pulled pipe. Ran tubing to 155 feet and cemented with 90 sack to surface.

Name of Plugging Contractor R.R.A., INC. License No. 5656

Address 100 South Main, Suite 510, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.R. Abderhalden


STATE OF Kansas COUNTY OF Sedgwick, ss.

R.R. Abderhalden (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) R.R. Abderhalden

(Address) 100 S. Mian, Suite 510, Wichita, KS



SUBSCRIBED AND SWORN TO before me this 24th day of November, 19 2003

Verdelia Lewis
Notary Public

My Commission Expires: 6-6-06

5-19-72

Mid Continent Petroleum Corp.

D. J. Sullivan #25 VDV

11816L

Well Data

(Source: Records in VIRGIL Field Office)

WELL: Sullivan #25

Date Drilling Started: 6-18-46

Date of First Production: 7-16-46

TREATMENT: 2000 gal acid

SURFACE CASING: 9 5/8" 24 # NF @ 24' w/ 15 sy

PRODUCTION CASING: 7" 24 # NF @ 1781' w/ 50 sy

Top Miss Lime:

Top of Pay:

Well T.D. 1813

Comp. Interval 1781-1813 (OH)

COMP. TEST P115 BOPD + 8 BOPD

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 04 2003

CONSERVATION DIVISION
WICHITA, KS