

4-032083

9-1

E-26,028

API Number: 15-153-20,755-00-01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

C NE NW /4 SEC. 33, 01S, 35 W
4620 feet from S section line
3300 feet from E section line

Operator license# 5140 Lease: Reeh Well # 2

Operator: Frontier Oil Company County: Rawlins

Address: 125 N. Market - Suite 1720
Wichita, Kansas 67202
Well total depth 4490 145.93 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 302 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 1 Month: September Year: 1995

Plugging proposal received from: Dick Parker

Company: Frontier Oil Company Phone:

Were: Order 250 sxs 60/40 pozmix - 10% gel - 200# hulls.

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1995
09-15-95
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:00 P.M., Day: 1, Month: September, Year: 1995

Actual plugging report: 8 5/8" set at 302' cwc with 175 sxs. 4 1/2" set at 4479' with 200 sxs. PBTB 4330'. Prod. Perfs. at 4228' - 4384' - 4228' - 4240'. Plug back to 4150' with 4 sxs on plug with bailer. Free point with one shot, recovering 2100' of casing. Mixed and pumped down casing 105 sxs cement with 200# hulls mixed in. Pulled casing to 240' circulated with 70 sxs. Pulled casing topped off with 5 sxs. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO
Plugged through TUBING, CASING. Elevation: GL

did not observe the plugging.

Carl Goodrow
(agent)

Form CP-2/3

INVOICED

DATE OCT 04 1995

INV. NO. 43637