

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01705-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 21-18S-10W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: APPEL Well #: 3  
County: RICE Total Vertical Depth: 3229 feet

Operator License No.: 31327  
Op Name: PAULEY, GARY DBA PAULEY OIL  
Address: PO BOX 163  
HOLYROOD, KS 67450

PROD Size: 5.5 feet: 3228 150 SX CMT  
SURF Size: 8.625 feet: 253 200 SX CMT

*B10494*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/10/2004 10:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: GARY PAULEY Company: GARY PAULEY DBA/ PAULEY OIL Phone: (785) 252-3286

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
MAY 26 2004

WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/10/2004 12:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Ran tubing to 485' and encountered blockage. Began power-swivel and drilled down to 1199'. Perforated at 1195', 900', and 303'. Ran tubing down hole to 954' and encountered obstruction. Pumped 75 sacks of cement. Pulled tubing to 900' and pumped 35 sacks of cement. Pulled tubing to 303' and circulated cement to surface.

60/40 posmix with 4% gel.

Remarks: COPELAND CEMENT #24423

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE 5-28-04  
INV. NO. 2004061617