

062347

2-18

153-20,774-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- \_\_\_\_\_  
NW, SEC. 33, T 1 S, R 35 W/EX  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Reeh Well # 3

Operator: Frontier Oil Company

County Rawlins 143.00

Name & Address 125 N. Market Suite 1720

Well Total Depth 4400 feet

Wichita, Ks. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

George A. Angle 316-263-1201

Surface Casing: Size 8 5/8 feet 298 w/170

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 125 N. Market Wichita, Ks. 67202

Company to plug at: Hour: 10:00AM Day: 13 Month: Feb. Year: 19 91

Plugging proposal received from Rick Hennesy

(company name) Red Tiger Drilling (phone) 316-263-1201

were: order 190 sks 60/40 poz 6% gel 3% cal cl 1 sk f.c. and 8 5/8 plug.

Spot with drill pipe w/no less than 36 vis mud between all pugs w/good

circulation and no fluid loss.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None xx

Operations Completed: Hour: 9:00 AM Day: 18 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3150 w/25 sks

2nd plug at 2330 w/100 sks 1 sk f.c.

3rd plug at 350 w/40 sks

4th plug at 40 w/10 sks

15 sks in rathole.

RECEIVED

STATE CORPORATION COMMISSION

MAR - 5 1991

3-5-91  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Allied Cement

(If additional description is necessary, use BACK of this form.)

INVOICED

(If you did not observe this plugging.

DATE 3-11-91

Signed Gilbert G. Scheck (TECHNICIAN) E.201

INV. NO. 31105