

4-032084

8-31

API Number: 15-153-20,752 -00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

C NW NW /4 SEC. 33, 01S, 35 W  
4620 feet from S section line  
4620 feet from E section line

Operator license# 5140

Lease: Reeh Well # 1

Operator: Frontier Oil Company

County: Rawlins

Address: 125 N. Market - Suite 1720  
Wichita, Kansas 67202

Well total depth 4445 144.46 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 7/8 Inch @ 308 feet

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 31 Month: August Year: 1995

Plugging proposal received from: Dick Parker

Company: Frontier Oil Company Phone: \_\_\_\_\_

Were: Order 250 sxs 60/40 pozmix - 10% gel - 200# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 15 1995

9-15-95

CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ ], Part[  ], None[ ]

Completed: Hour: 9:00 P.M., Day: 31, Month: August, Year: 1995

Actual plugging report: 8 5/8" set at 308' cwc with 190 sxs. 4 1/2" set at 4417' with 200 sxs. Prod. Perfs at 4214' - 4370'. Plug back to 4150' with 4 sxs on plug with bailer. One shot recovered 2342' of casing. Mixed and pumped down casing 105 sxs cement blend with 200# hulls mixed in. Pulled to 400' circulated with 125 sxs cement blend. Pulled casing, topped off with 15 sxs. Plug complete.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES \_\_\_\_\_ NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES \_\_\_\_\_, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I did  / did not  observe the plugging.

Carl Goodrow  
(agent)

Form CP-2/3

INVOICED

DATE SEP 22 1995

43564

HO