

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10054-00-00
Spot: SWSESW Sec/Twnshp/Rge: 27-29S-14W
330 feet from S Section Line, 1650 feet from W Section Line
Lease Name: KERR FH Well #: 2
County: PRATT Total Vertical Depth: 4530 feet

Operator License No.: 32047
Op Name: MICA ENERGY CORP.
Address: P. O. BOX 20707
OKLAHOMA CITY, OK 73156

CIBP Size: feet: 4500 WITH 2 SX CMT
PROD Size: 5.5 feet: 4523 WITH 200 SX CMT
SURF Size: 8.625 feet: 763 WITH 300 SX CMT

#147²³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2004 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: CIBP @ 4510' WITH 2 SX CMT. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2004 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4530'. CASING LEAK SQUEEZED AT 2937' WITH 225 SX CMT. SET CIBP @ 4500' & PUT 2 SX CMT ON TOP OF PLUG THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4523	4530	OH	

RECEIVED
MAY 27 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1730' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
MAY 25 2004
KCC Dodge City

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 5.27.04
BILL NO. 200406114

Form CP 275