

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21195-00-01
Spot: W2NWSW Sec/Twnshp/Rge: 4-35S-21W
1980 feet from S Section Line, 360 feet from W Section Line
Lease Name: TUTTLE Well #: 3-4
County: CLARK Total Vertical Depth: 5800 feet

Operator License No.: 5050
Op Name: HUMMON CORPORATION
Address: 950 N. TYLER
WICHITA, KS 67212

CIBP Size: feet: 4375 WITH 2 SX CMT
PROD Size: 4.5 feet: 5730 WITH 285 SX CMT
SURF Size: 8.625 feet: 384 WITH 300 SX CMT

\$188⁵⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/20/2004 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: CIBP @ 4375' & 2 SX CMT. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 05/20/2004 12:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5648'. CIBP @ 4375' WITH 2 SX CMT. 1ST PLUG PULL TO 900' & SPOT 10 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 400' & PUMP 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
5588	5591		
5575	5579		
4434	4442		

RECEIVED
MAY 27 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4000' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED

DATE 5.27.04
INV. NO. 200406164

Form CS-1/3