

4-070147

5-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-153-20,309-00-00

C NE NE /4 SEC. 30, 01 S, 36 W
4620 feet from S section line
660 feet from E section line

Operator license# 4526 (4/95) ^{OK} ^{HD Deines}
Operator: Evergreen Operating Corporation

Lease: Hatch Well # 1-30
County: Rawlins 146,90

Address: 1401 17th Street-Suite #1200
Denver, CO 80202

Well total depth 4520 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 237 feet
W/250 sxs.

ABAND. oil well, Gas well X, Input well, SWD, D&A

Plugging contractor: Company Tools License# 4526

Address: 1401 17th Street - Suite #1200 - Denver, CO 80202

Company to plug at: Hour: 10:00 A.M. Day: 13 Month: May Year: 1999

Plugging proposal received from: John J. Tanigawa

Company: Evergreen Operating Corporation Phone: 303-298-8100

Were: 4 1/2" casing set at 1392' w/100 sxs.

Perfs: 1272' - 1336'.

Past operator agreed to plug well. Approved by M.L.K.

Ordered out 150 sxs 60/40 pozmix - 10% gel with 400# hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:30 P.M. Day: 13, Month: May, Year: 1999

Actual plugging report: Allied Cementing Company, Inc. (Oakley) hooked up to 4 1/2" casing.

Well head pressure 250#. Pumped 70 sxs 60/40 pozmix - 10% gel with 200# hulls.

Max. P.S.I. 500#. S.I.P. 500#. Waited on welder one hour. Pressure increased to 800#.

Hooked up to backside and Allied pumped 50 sxs 60/40 pozmix - 10% gel with 100# hulls.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING X. Elevation: 3290 GL

I did [X] / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

RECEIVED
STATE OF KANSAS
06-04-1999
JUN 4 1999

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 6-9-99

INV. NO. 61014