



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-153-30 109-00-00

RECEIVED
STATE CORPORATION COMMISSION
12-14-1965
DEC 14 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Don Woolley of Ben J. Taylor has this

date requested permission to plug the following described well:

Mr. Woolley guarantees payment of the plugging fee.

Operator's full Name: Ben J. Taylor.

Complete Address: 2809 North-West Expressway, Oklahoma City, Okla.

Lease Name: Frisbie Well No. 1

Location: SE-SE Sec. 25 Twp. 1 Rge. (E) (W) 36

County Rawlins Total Depth 4905 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Woolley was instructed to plug the well as follows:

201'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

" " 185' and 20 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent