

State of Kansas



15-153-01000-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 14 1966  
6-14-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Empire Drilling Company has this date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company.

Complete Address: 650 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Skolout Well No. 1

Location: CNE-SE Sec. 35 Twp. 1 Rge. (E)(W) 35

County Rawlins Total Depth 4420 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Helberg was instructed to plug the well as follows:

- 240'--8 5/8" Surface pipe, cement circulated.
- Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.
- " " " 240' and 20 Sx. cement.
- " " " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

M. L. Nichols  
Conservation Division Agent