

State of Kansas



15-153-20022-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1968
CONSERVATION DIVISION
Wichita, Kansas
17-12-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: T. L. Ferrier.

Complete Address: 300 Schweiter Building, Wichita, Kansas.

Lease Name: Mary Sabatka Well No. 1

Location: CSW-SE Sec. 33 Twp. 1 Rge. (E)(W) 35

County: Rawlins Total Depth 1435 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

314'--8 5/8" Surface pipe, cement circulated with 275 Sx.
Top of Dakota section @ 1475'.

Circulate hole with heavy mud. Pull DP to 1700' and displace 100 Sx.
cement thru DP. Pull DP to 340' and displace 20 Sx. cement thru DP.
Pull DP. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent