



15-153-20090-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1970
CONSERVATION DIVISION
Wichita, Kansas
11-9-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Inc., has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Husky Oil Company of Delaware,

Complete Address: Box #380, Cody, Wyoming.

Lease Name: Husky-Reeh Well No. 3-31

Location: CNE-NW Sec. 31 Twp. 1 Rge. (E)(W) 35

County: Rawlins Total Depth 4530' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

324'--8 5/8" Surface casing cement circulated with 250 Sx.

Circulate hole with heavy mud. Pull DP to 2350' and displace 100 Sx.

cement thru DP. Pull DP to 330' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent