

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-153-20,752-00-00

LEASE NAME Reeh

WELL NUMBER #1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 33 TWP. 1S RGE. 35 (X) or (W)

COUNTY Rawlins

Date Well Completed 6-18-90

Plugging Commenced 8-31-95

Plugging Completed 8-31-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Frontier Oil Company

125 North Market, Suite 1720

ADDRESS Wichita, KS 67202

PHONE#(316) 263-1201 OPERATORS LICENSE NO. 5140

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-31-95 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Lansing-KC Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4445'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	308'	-0-
				4 1/2"	4417'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Set a drillable 4 1/2" cast iron plug at 4090' & pumped 4 sx com. cem. on top of plug. Shot off 4 1/2" csg. at 2347' & pumped 105 sx 60-40 poz, 10% gel & 200# hulls down 4 1/2" csg. Pulled 4 1/2' csg. up to 400' from surface & pumped 125 sx 60-40 poz, 10% gel, down 4 1/2" csg. Cem. did circ. Pulled 4 1/2" csg. out of hole & loaded hole w/ 15 sx 60-40 poz, 10% gel cement. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Express Well Service

STATE RECEIVED  
CORPORATION COMMISSION

Address P. O. Box 426, Victoria, KS 67671

SEP 07 1995 9-7-95

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Frontier Oil Company

STATE OF KANSAS COUNTY OF SEDGWICK

CONFIDENTIAL  
WICHITA KANSAS

Jean Angle (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jean Angle

(Address) 125 North Market, Suite 1720  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1995

**JEAN HOLLAR**  
Notary Public - State of Kansas  
My Appt. Expires May 5, 1998

Jean Hollar  
Notary Public

My Commission Expires: 5-5-98