

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-153-20,755-00-01

LEASE NAME Reeh

WELL NUMBER #2

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 33 TWP. 1S RGE. 35 (E) or (W)

COUNTY Rawlins

Date Well Completed 6-18-90

Plugging Commenced 9-1-95

Plugging Completed 9-1-95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Frontier Oil Company

ADDRESS 125 North Market, Suite 1720
 Wichita, KS 67202

PHONE#(316) 263-1201 OPERATORS LICENSE NO. 5140

Character of Well SWD EOR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-1-95 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4490

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	302'	-0-
				4 1/2"	4479'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Set a 4 1/2" drillable cast iron plug at 4180' & pumped 4 sx com. cem. on top of plug. Shot off 4 1/2" csg. at 2200' & pumped 105 sx 60-40 poz, 10% gel, & 200# hulls down 4 1/2" csg. Pulled 4 1/2" csg. up to 240' from surface & pumped 70 sx 60-40 poz, 10% gel down 4 1/2" csg. Cem. did circ. Pulled 4 1/2" csg. out of hole & loaded hole w/ (if additional description is necessary, use BACK of this form.) 5 sx 60-40 poz, 10% gel.

Name of Plugging Contractor Express Well Service LICENSE NO. _____

Address P. O. Box 426, Victoria, KS 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Frontier Oil Company

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jean Angle (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jean Angle

(Address) 125 North Market, Suite 1720
 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1995

JEAN HOLLAR
 Notary Public - State of Kansas
 My Appt. Expires May 5, 1998

My Commission Expires: 5-5-98

Jean Hollar
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 07 1995
 09-07-95
 WICHITA, KANSAS