

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-193-20023-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rawlins County. Sec. 35 Twp. 1S Rge. (E) 35 (W)

Location as "NE/CNW/SW" or footage from lines C NW SE

Lease Owner Chief Drilling Co., Inc.

Lease Name SKOLOUT Well No. 1

Office Address Box 797 - Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/18 19 68

Application for plugging filed 7/18 19 68

Application for plugging approved 7/18 19 68

Plugging commenced 7/18 19 68

Plugging completed 7/18 19 68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker - Victoria, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4407 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	257	8-5/8"	257	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

100 sacks cement @ 1200'
Wooden plug set @ 265'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1968
CONSERVATION DIVISION
Wichita, Kansas

7-22-68

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF BARTON, ss.
Thomas G. Wesselowski (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas G. Wesselowski
Box 797 - Great Bend, Kansas 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19 68

Carmen R. Cook
Carmen R. Cook, Notary Public.

Dec. 12, 1970



15-153-2002300-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1968
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas 67530

SKOLOUT #1
C NW SE Sec. 35-1S-35W
Rawlins County, Kansas

7-22-68

Contractor: Chief Drilling Co., Inc.

Commenced: 7-8-68
Completed: 7-18-68

Casing Record: 8-5/8" set @ 257' w/200 sacks 60/40 Pozmix, 2% Gel.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>	<u>FORMATION TOPS</u>	
			3218 Gr.		
			3220 D.F.		
			3223 K.B.		
				<u>SAMPLE</u>	<u>LOG</u>
Post Rock & Sand	0	257			
Shale	257	430			
Shale & Sand	430	1910			
Shale & Shells	1910	2650			
Shale, Shells & Conglomerate Sand & Lime	2650	2780			
Red Bed & Shale	2780	3058	Anhydrite	3058	
Anhydrite	3058	3065	Heebner	4079	4078 - 855
Shale & Lime	3065	4164	Lansing	4128	4132 - 909
Lime	4164	4407	Base Kansas City		4394 - 1171
Total Depth	4407		Total Depth	4407	4409 - 1186

STATE OF KANSAS, COUNTY OF BARTON) SS


I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NW SE Section 35-1S-35W, Rawlins County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Thomas G. Wesselowski, Geologist

Subscribed and sworn to before me this 19th day of July, 1968.

Carmen R. Cook, Notary Public



Commission Expires: Dec. 12, 1970.