

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. 1-12-5

ORIGINAL

API NUMBER ¹⁵ 165-21,757-00-00

LEASE NAME Merry

WELL NUMBER 1

4620 Ft. from S Section Line

3760 Ft. from E Section Line

SEC. 10 TWP. 18 S RGE. 18 W (R) or (W)

COUNTY Rush

Date Well Completed 3/23/04

Plugging Commenced 1:15AM 3/23/04

Plugging Completed 3:15AM 3/23/04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR GLOBE OPERATING, INC.

ADDRESS P.O. Box 12 Great Bend, KS 67530

PHONE (620) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/19/04 (date)

by Jim Holland (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.D. 3888'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	<u>1250</u> <u>1249</u>	<u>8 5/8</u>	<u>1250</u> <u>1249</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
1st Plug @ 1300'W/50sks 15sks In Rat Hole Circulated 1st Plug 15 Minutes With 50Vis Mud
2nd Plug @ 600'W/50sks Plugs Displaced with mud
3rd Plug @ 40'W/10sks Total 135sks 60/40 Poz 6% Gel w/1#CE/sk By Allied Cementing
10sks In Mouse Hole Completed @ 3:15AM 3/23/04

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GLOBE OPERATING, INC.

STATE OF Kansas COUNTY OF Barton, ss.

Richard Stalcup (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Richard Stalcup


(Address) P.O. Box 12, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 28th day of April, 19 2004

M. Lynne Wooster
Notary Public

My Commission Expires: 4-02-07

RECEIVED
APR 29 2004
KCC WICHITA



Form CP-1
Revised 05-88

Jim