

STATE OF KANSAS
STATE CORPORATION COMMISSION
301 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20991-00-00

LEASE NAME Susan

WELL NUMBER #1

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 33 TWP. 33 RGE. 30W (E) or (W)

COUNTY Meade

Date Well Completed

Plugging Commenced 5-12-04

Plugging Completed 5-18-04

RECEIVED

MAY 27 2004

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR BEAR PETROLEUM, INC.

ADDRESS P.O. Box 438 Haysville, Kansas 67060

PHONE# (316) 524-1225 OPERATORS LICENSE NO. 4419

Character of Well Oil

Well, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on 5-25-04 (date)

Steve Middleton (KCC District Agent's Name)

ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5850' 6650'

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surf Prod			1535'	8-5/8"	1535'	None
			6649'	4-1/2"	6649'	2750'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 5770' and 4 sacks cement. Cut casing loose @2750', pulled up to 1550', pumped 10 sacks gel, 100# hulls, 50 sacks cement, pulled up to 600', pumped 40 sacks cement w/100# hulls, pulled up to 40' and circulated 25 sacks cement to surface 60-40 pos. Plugging Complete. 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
I, above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 25th day of May, 2004

[Signature]
Notary Public

My Commission Expires:



Form C
Revised 05-