

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20309-00-00

LEASE NAME HATCH 1-30

WELL NUMBER 1-30

766 Ft. from S Section Line

766 Ft. from E Section Line

SEC. 30 TWP. 1 RGE. 36 (E) or (W)

COUNTY RAWLINS

Date Well Completed 1-30-78

Plugging Commenced 5-13-1999

Plugging Completed 5-18-1999

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR EVERGREEN OPERATING CORP

ADDRESS 1401 17TH STREET SUITE 1200

PHONE# (303) 298-9100 OPERATORS LICENSE NO. 4526

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-13-1999 (date)

by CARL GOODROWE (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? NO - SEE CP-1 (5-3-99)

Producing Formation NIORARA Depth to Top 1272 Bottom 1336 T.O. 1340

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
| NIORARA | GAS | 0 | 237 | 8-5/8" | 237 | NONE |
| | | 0 | 1340 | 4-1/2" | 1340 | NONE |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
MOVE IN/RIG UP ALLIED CEMENTING. MIX 200 SX 60/40 POZ CEMENT W/ 10X GEL AND 200# HULLS. NU TO CASING HEAD. PUMP CEMENT DOWN 4-1/2" CASING - PRESSURED UP TO 300 PSI. SI. MIX 70 SX 60/40 POZ CEMENT W/ 10X GEL AND 100 # COTTON SEED HULLS. NIPPLE UP TO 2" VALVE AND PUMP DOWN ANNULUS. PRESSURE TO 200#. WAIT ON CEMENT. CUT CASING. CASING HEAD 5 FEET BELOW GROUND. CLEAN LOCATION.

Name of Plugging Contractor ALLIED CEMENTING License No. _____

Address P.O. Box 31, RUSSELL, KS 67655

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EVERGREEN OPERATING CORP

STATE OF COLORADO COUNTY OF DENVER, ss.


JOHN J. TANIGAWA (Employee of Operator) or (Operator) or above-mentioned _____, being first duly sworn on oath, says: That I have knowledge of the facts stated in the above matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 1401 17TH STREET, STE 1200, DENVER CO 80202

AS WITNESSED AND SWORN TO before me this 17th day of May, 1999

Janet S. Yamamoto
Notary Public

My Commission Expires: November 30, 2001



MAY 19 1999
05-19-1999
CONSERVATION DIVISION
Wichita, Kansas