


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD
15-153-00053-00-00

RAWLINS COUNTY KAS County. Sec. 13 Twp. 1S Rge. 36W (E) (W)
SW SW SE



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner TWIN DRILLING, INC.
Lease Name VACHUTA Well No. 1
Office Address 719 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 4th, 1959 19
Application for plugging filed December 4th, 1959 19
Application for plugging approved December 4th, 1959 19
Plugging commenced December 4th, 1959 19
Plugging completed December 4th, 1959 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5052' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	360'	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 600' set plug with 20 sx cement. Filled with heavy mud to 300' set plug with 20 sx cement. Filled with heavy mud to 40' set solid bridge with 10 sx cement to base of cellar. Job complete 12-4-59

RECEIVED
STATE CORPORATION COMMISSION
12-10-1959
DEC 10 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
James L. Downing (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Downing
James L. Downing, of K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 59

My commission expires August 11th, 1962.
Patricia M. Edwards, Notary Public.



15-153 - 00053-00-00
DRILLER'S WELL LOG

OPERATOR: TWIN DRILLING, INC.
 1005 Central Building
 Wichita 2, Kansas

WELL NAME: #1 VACHUTA
 LOCATION: SW SW SE
 Sec. 13-18-36W
 RAWLINS CO, KANSAS

CONTRACTOR: K & E DRILLING, INC.
 719 UNION CENTER BLDG.
 WICHITA, KANSAS

COMMENCED: November 22nd, 1959

CASING RECORD: 8-5/8" @ 360' (265 sx cmt)

COMPLETED: December 4th, 1959

ELEVATION: unknown

ROTARY TOTAL DEPTH: 5052'

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Clay & Shale	180
Gravel & Sand	200
Shale	245
Sand (hard)	265
Sand & Shale	360
Shale	1900
Sand & Shale	2375
Shale & Shells	2510
Shale & Lime	2680
Shaly Pyrite	2710
Shale	2805
Lime & Shale	2945
Anhydrite	2980
Lime & Shale & Red Bed	3240
Shale	3400
Lime	3540
Lime & Shale	4080
Lime	4200
Shale	4261
Lime	4505
Lime & Shale	4884
Lime & Shert	4994
Sahle & Lime	5012
Arbuckle	5052
R.T.D.	5052'

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 10 1959
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATION

State of KANSAS }
 County of SEDGWICK } ss:

I, James L. Downing, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

and sworn to before me this 7th day of December, 1959

My Commission expires August 11th, 1962.

James L. Downing
 James L. Downing
Patricia M. Edwards
 Patricia M. Edwards Notary Public.

