

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 12/91

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-023-20,260-00-00 (unique identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, please give spud or completion date.

WELL OWNER/OPERATOR Joseph H. Strabala OPERATOR'S LICENSE NO. 9041

ADDRESS 312 E. Uintah St. PHONE # (719) 635-7807

LEASE Waters WELL # 1 SPOT/LOCATION 1950 S & 1230 E COUNTY Cheyenne

SEC. 32 T. 01 R. 38 (E/W) ELEV. 3316 (G/L/KB) T.D. 4800 P.B.T.D. 4350

Check One:

OIL WELL GAS WELL D & A SWD or ENHR WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 337 CEMENTED WITH 215 60/40 poz SACKS

CASING SIZE 4 1/2 SET AT 4747 CEMENTED WITH 225 60/40 poz SACKS

PERFORATED AT 4356 - 4331

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE No

PROPOSED METHOD OF PLUGGING Hooked-up to 4 1/2 casing. Pumped in 25 sxs. 60/40 pozmix followed with 100 sx. 60/40 posmix with 1/4# F.C. plus 500# hulls. Max. P.S.I. 2200#. Shut in @ 2100#. Hooked-up to 8 5/8 S.P. Pumped in 225 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 100# hulls. Max P.S.I. 800 #. Shut in 300 #.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes
If not explain why? _____

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Done April 1, 1992 at 2:30 PM

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dennis L. Hamel (Hays, Kans) PHONE # () _____

ADDRESS _____

PLUGGING CONTRACTOR _____ LICENSE NO. _____

ADDRESS _____ PHONE # () _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Joseph H. Strabala

DATE: May 15, 1992