

6 030546

API NUMBER 15-023-20018-00-00 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE SEC. 13, T. 1 S, R. 38 W
3520 feet from S section line
1760 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7311

Lease Name EUGENE HAM Well # 1

Operator: SHAKESPEARE OIL CO INC.

County CHEYENNE 151.00

Name & Address P.O. Box 670

Well Total Depth 4646 PB 1605' feet

SALEM, ILLINOIS

Conductor Pipe: Size _____ feet

62881

Surface Casing: Size 8 5/8 feet 212'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS 67524

Company to plug at: Hour: AM Day: 22 Month: 8 Year: 19 85

Plugging proposal received from RONNIE

(company name) KELSO CASING (phone) _____

were: 8 5/8 SET @ 212' CUR. 4 1/2 SET @ 1605' w/ 150 SX. PERF 1222-48'

ORDER SAND & COM. CMT. RECOVERED 1000' OF 4 1/2" CASING. ORDER

180 SX. 60/40 PZ 6% GEL 3% CU 20 SX. GEL 3 SX. HULLS B.J. TITON CMT. CO

WEBB WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:40AM Day: 22 Month: 8 Year: 19 85

ACTUAL PLUGGING REPORT Dump SAND & 4 SX. COM. CMT. ON PBD TO 1200' PULL PIPE

Pump. Down 8 5/8 w/ 3 HULLS 20 GEL. 180 SX. CMT MIX. MAX. PSI 700[#]

CLOSE IN 400[#] PLUG. COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

03
09-30-1985 ← SEP 3 1985

09-08-1985
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(if additional description is necessary, use BACK of this form.)

INVOICED (and bill) observe this plugging.

SEP 10 1985

DATE 9963

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 9963