

4-19

4-041668

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 S. MARKET, ROOM #2078  
WICHITA, KANSAS 67202

API number: 15-023-20,026-00-01  
C NE NW /4 SEC. 11, 01 S, 38 W  
1980 feet from S section line  
1980 feet from W section line

Operator license# 9860 Lease Ketler well # 1

Operator: Castle Resources, Inc. County Cheyenne *145.86*

Address: 1200 E. 27th Street Well total depth 4488 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 218 feet  
w/240 sxs.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License# \_\_\_\_\_

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00P.M. Day: 19 Month: April Year: 95

Plugging proposal received from: Jerry Green

Company: Castle Resources, Inc. Phone: \_\_\_\_\_

Were: 4 1/2" casing set at 4486' w/250 sxs. cement. Perfs. at 4312' - 4108'. Anhy. @ 3080' - Dakota @ 2240' - W.L.M. @ 4165' - T.O.F. @ 1500'. Found free point at 1550'. Ordered 300 sxs. 60/40 pozmix - 6% gel - 7 sxs. gel - 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 2:00A.M., Day: 19, Month: April, Year: 95

Actual plugging report: Perf. casing at 3080' and 2240'. Hooked- up to 4 1/2" casing. Pumped 25 sxs. cement with 300# hulls, followed with 7 sxs. gel, followed with 100 sxs. cement - displaced cement to 1650'. Cut-off casing at 1487'. Pulled casing to 800' and pumped 75 sxs. cement. Pulled casing to 240' and circulated cement to surface with 100 sxs. cement. Pulled rest of casing and filled surface pipe to top.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES  , CALC \_\_\_\_\_ , NO \_\_\_\_\_ Dakota plug: YES  , NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_ , CASING  . Elevation: \_\_\_\_\_ GL

I did  / did not  observe the plugging.

*Dennis L. Hamel*  
(agent)

**INVOICED**  
DATE 5-2-95  
INV. NO. 42719

*Rec'd 4-28-95*