

4- 041361

4-1

36 R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-023-20,260-00-00

SW NE SE /4 SEC. 32, 01 S, 38 W
1950 feet from S section line
1230 feet from E section line

Operator license# 9041

Lease Waters well # 1

Operator: Joseph H. Strabala

County Cheyenne

Address: 312 E. Unitah St.
Colorado Springs, Colo 80903

Well total depth 4800 feet ^{156.00}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 337 feet
w/215 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00A.M Day: 1 Month: April Year: 92

Plugging proposal received from: Joseph H. Strabala

Company: Joseph H. Strabala Phone:

Were: 4 1/2" casing set @ 4747'. Perf. @ 4356' - 4331'.
Anhy. @ 3270'. W.L.M. 4350'. T.O.F. @ 2200'.
Order 350 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 600# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:30P.M., Day: 1, Month: April, Year: 92

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped in 25 sx. 60/40 pozmix followed with 100 sx. 60/40 pozmix with 1/4# F.C. plus 500# hulls. Max. P.S.I. 2200#. Shut in @ 2100#.
Hooked-up to 8 5/8" S.P. Pumped in 225 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 100# hulls. Max. P.S.I. 800#. Shut in 300#.

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1992
04-15-1992
CONSERVATION DIVISION
Wichita, Kansas

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging. Dennis L. Hamel

DATE 3-5-92

INV. NO. 35128

(agent)

Form CP-2/3

M.H.