

12-31

66R

4-071024

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-023-20,323-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1993
O1-12-1993
CONSERVATION DIVISION
WICHITA, KS

SW NW NE /4 SEC. 10, 01 S, 38 W
4125 feet from S section line
2310 feet from E section line

Operator license# 30137 Lease Christianson well # 5

Operator: M & C Oil Company County Cheyenne

Address: P.O. Box 647 Well total depth 4585 feet ^{149.01}
Holdridge, NE 68949 Conductor Pipe: 0 inch @ 0 feet
Paul Christianson Surface pipe 8 5/8 Inch @ 211 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling, Inc. License#

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 31 Month: December Year: 92

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling, Inc. Phone: 308-995-5962

Were: 8 5/8" - 211' S.P. cwc. w/190 sx. 60/40 pozmix - 2% gel. - 3 sx. C.C. By Allied Cement. Elv. 3038' - Anhy. 3014' - Ft. Scott well. No circulation problems. Mud condition - 45 vis. - 9.3 wt. - 7.2 water loss. Proposal 190 sx. 60/40 pozmix - 6% gel. and 1 sx. F.C. Spot with drill stem, heavy mud between all plugs. 25 sx. @ 3030' - 100 sx. w/1 sx. F.C. @ 2180' - 40 sx. @ 260' - 10 sx. @ 40' - 15 sx. in rathole. Circulate.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:15P.M., Day: 31, Month: December, Year: 92

Actual plugging report: Murfin ordered 190 sx. 60/40 pozmix - 6% gel. - 1 sx. F.C. - circulate hole - spotted and displaced all cement through tubing, with heavy mud between all plugs.

- 1st. plug @ 3030' w/25 sx. cement.
- 2nd. plug @ 2180' w/100 sx. cement w/1 sx. Flo-cele.
- 3rd. plug @ 260' w/40 sx. cement.
- 4th. plug @ 40' w/10 sx. cement.
- 15 sx. in Rathole (circulate)

Remarks: Cement by Allied.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 3033 GL

I did not observe the plugging.

Marion J. Schmidt
(agent)

DATE FEB 02 1993

INV. NO. 37276

1-31 APR 02 1993