

12-9

6 070734

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW NW SE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 023-20,263 -00-00
SEC. 3, T 1 S, R 38 (W/E)

1650 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8682

Lease Name Haines Well # 3-20

Operator: Golden Eagle Drilling
Name & Address: Box 55
McCook, Neb. 69001

County Cheyenne 147.88

Well Total Depth 4550 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 150

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Golden Eagle Drilling License Number _____
Address Box 55, McCook, Neb. 69001

Company to plug at: Hour: AM Day: 9 Month: Dec Year: 19 88

Plugging proposal received from Dave Paschel, Darwin Pierson

(company name) Golden Eagle Drilling (phone) _____

were: 8 5/8" 150' S.P. cwc w/100 sks 60/40 Poz 2% Gel 3% Cal Cl . By Halco. K.C. Fort

Scott Well-Flv. 3026' - Anhy 3015'. No circulation problems. Mud condition 50 viscosity.

9.4 weight, water loss 6.4. Proposal 215 sks 60/40 Poz 6% Gel 3% Cal Cl and 8 5/8" plug.

Spot with drill stem circulate heavy mud between all plugs. 30 sks at 3030'. 100 sks at

2175'. 50 sks at 270'. 10 sks at 40' 15 sks rathole, cir 10 sks in mouse hole (cir)

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 8:00AM Day: 9 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Ordered 215 sks 60/40 Poz 6% Gel 3% Ca Cl and 8 5/8" plug.

~~Spotted with drill stem. Circulated hole, heavy mud between all plugs.~~

1st plug at 3030' w/30 sks cement 10 sks in mousehole (cir)

2ng plug at 2175' w/100 sks w/1 sk F.C. 15 sks in rathole (cir)

3rd plug at 270' w/50 sks cement Cemented by Halliburton Cement

4th plug Hulls plug at 40' w/10 sks cement

Remarks: (If additional description is necessary, use BACK of this form.)

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE DEC 19 1988

Signed *Marion J. Schmidt*
(TECHNICIAN)
Marion J. Schmidt

D

INV. NO. 23392