

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20254-00-01
Spot: SESESE Sec/Twnshp/Rge: 3-1S-38W
330 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: CHRISTENSEN Well Number: 3-32
County: CHEYENNE Total Vertical Depth: 5013 feet

Operator License No.: 3152
Op Name: POE SERVICING INC
Address: PO BOX 115
OBERLIN, KS 67749

Production Casing Size: 4.5 feet: 4502 w/225 sxs cmt
Surface Casing Size: 8.625 feet: 152 w/100 sxs cmt

\$162⁹²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2003 11:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: RUBY POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 10% gel - 400# hulls.
Plug thru tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/25/2003 2:10 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforations 4028' to 4403'. TD 5013'. PBTD 4502'. Junk in hole at 2440'.
8 5/8" surface casing set at 151' w/100 sxs cement.
4 1/2" production casing set at 4502' w/225 sxs cement.
Ran tubing to 2000' - pumped 50 sxs cement.
Pulled tubing to 1000' - pumped 40 sxs cement with 100# hulls. Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 100 sxs cement with 200# hulls.
Connected to 8 5/8" surface casing - pumped 50 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 100#.
Connected to 4 1/2" production casing - pumped 40 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.

RECEIVED
NOV 17 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED
DATE 11-18-03
NO. 2004060787

Form CP-2/3

NOV 06 2003

BJ-TITAN SERVICES COMPANY

15-023-20254-00-01

REMITTANCE ADVICE

INVOICE DATE
04/17/89

DIRECT BILLING INQUIRIES TO:	TERMS	REMIT TO:
713-895-5821	NET AMOUNT DUE 30 DAYS FROM DATE OF INVOICE	BJ-TITAN SERVICES P.O. BOX 100006 HOUSTON, TX 77212

PAGE	INVOICE NO.
1	SR116

GOLDEN EAGLE DRILLING

P.O. BOX 983

MC CORK #8606
10-20-89

NE 69001

AUTHORIZED BY
510078

WELL NUMBER : 3-32

CUSTOMER NUMBER : 10083002

PURCH. ORDER REF. NO.

LEASE NAME AND NUMBER	STATE	COUNTY/PARISH	CITY	DISTRICT NAME	DISTR. NO.
CHRISTENSEN WASHDOWN	14			OAKLEY	3520
JOB LOCATION/FIELD	MTA DISTRICT	DATE OF JOB	TYPE OF SERVICE		
		04/17/89	LAND-LONG STRING/PRODUC		

PRODUCT NUMBER	QUANTITY	DESCRIPTION	UNIT PRICE	U/M	EXTENDED PRICE
10102120	1.00	CEMENTING THRU TUBING 3001 TC	935.00		935.00
10102125	15.02	PLUS PER 100 FT BELOW 3000 FT	11.00		165.22
10109005	140.00	MILEAGE CHRG. FROM NEAREST BAS	1.10		154.00
10430508	1.00	4-1 1/2" TOP RUBBER PLUG	42.50	EA	42.50
10410504	225.00	CLASS "A" CEMENT	6.00	CF	1,350.00
10415049	159.00	A-2-4 CALCIUM CHLORIDE PELLETS	0.35	LB	55.65
10420145	4.23	BJ-TITAN GEL, SEMI-SOLIDS, BULK	6.75	CB	28.55
10428020	12.69	A-10 GYPSEAL	14.50	CB	184.27
10425010	500.00	MUD-SWEEP, WITH BJ-TITAN PUMPI	1.45	CL	725.00
10880085	204.00	MIXING CUSTOMERS MATERIALS	0.95		213.75
10940101	895.00	DRAYAGE, PER TON MILE	0.70		563.50
10409600	1.00	4 1/2 GUIDE SHOE (B)	104.00	GL	104.00
10409600	1.00	4 1/2 INSERT (D)	161.00	GL	161.00
10409600	1.00	4 1/2 BASKET (B)	120.00	GL	120.00
10409600	6.00	4 1/2 CENTRALIZERS (B)	41.75	GL	250.50
			SUBTOTAL		5,090.76
			DISCOUNT		1,303.72

RECEIVED
STATE CORPORATION COMMISSION
AUG - 1 1990
CONSERVATION DIVISION
Wichita, Kansas

ACCOUNT			
	4.0000 STATE TAX	2204.07	60.10
	1.000000 COUNTY TAX	2204.07	22.05

TAX EXEMPTION STATUS:

PAY THIS AMOUNT

3,767.24