

LEASE NAME Ketler

WELL NUMBER #1

1980' Ft. from S Section Line

1980' Ft. from E Section Line

SEC. 11 TWP. 1S RGE. 38 ~~XX~~ or (W)

COUNTY Cheyenne

Date Well Completed 11-27-87

Plugging Commenced 4-19-95

Plugging Completed 4-19-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Castle Resources Inc.

ADDRESS 1200 E. 27th Suite C, Hays, Kansas 67601

PHONE#(913) 625-5155 OPERATORS LICENSE NO. 9860

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 19, 1995 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation LKC-Topeka Depth to Top 4108' Bottom 4312' T.D. 4796'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	Shale	0	218	8 5/8	218	0
Surface to TD	Shale & Lime	0	4486'	4 1/2	4486	1487'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Perf. casing at 3080' and 2240'. Hooked up to 4 1/2" casing. Pumped 25sks cement with 300# hulls, followed with 7sks gel, followed with 100sks cement displaced cement to 1650'. Cut-off casing at 1487'. Pulled casing to 800' and pumped 75 sks cement. Pulled casing to 240' and circulated cement to surface with 100 sks cement. Pulled rest of casing and filled surface pipe to top.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. N/A

Address E. 8th, Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle Resources Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Jerry Green

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Hays, Kansas 67601



SUBSCRIBED AND SWORN TO before me this 25th day of April, 19 95

My Commission Expires: 7-2-95

Nancy Taggart  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
04-26-1995  
APR 26 1995

CONSERVATION DIVISION  
WICHITA, KANSAS