



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1963

6-11-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Cliff Perkins of Murfin Drilling Co., has this

date requested permission to plug the following described well:
Tenneco Oil Co.

Mr. Perkins guarantees payment of the plugging fee.

Operator's full Name: Tenneco Oil Company,

Complete Address: Box #163, Great Bend, Kansas.

Lease Name: Harrison Well No. 1

Location: CNE-SW Sec. 22 Twp. 1 Rge. (E) (W) 39

County Cheyenne Total Depth 4627 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Perkins was instructed to plug the well as follows:

206'--8 5/8" Surface Pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx cement.

" " 195 with 1/4 Sk hulls & 20 Sx cement.

" " 40' with 1/2 Sk hulls & 10 Sx cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent