

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

*R*

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-023-00010-00-00

File No. \_\_\_\_\_ County: CHEYENNE

Location: C NW NW Sec. 25 Twp. 1 Rge. 38 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 5130

I have this date completed supervision of plugging of:

Lease Name: Schraeder Well No. #1

Operator's Full Name: Badger Drillers Inc.

Complete Address: Tulsa, Okla.

Plugging Contractor: Same

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 1 P.M. Day 4 Month JUNE Year 59

The above well was plugged as follows:

Mudded BACK to 600' 20SX CEMENT - Mudded BACK to 340' 20SX CEMENT - Mudded BACK to 40' 10SX CEMENT TO BASE OF CELLAR. 340' 8 5/8" SURFACE CASING.

Signed: A. P. Johnson  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 25 T. 1 R. 38  
BOOK PAGE 63 LINE 23

RECEIVED  
06-17-1959  
JUN 17 1959

# BADGER DRILLERS, INC.

P.O. BOX 287 DIAMOND 3-9109  
TULSA 3, OKLAHOMA

FRED MADDOX  
WICHITA, KANSAS  
AMHURST 2-8347

FRED VEAIL  
GREAT BEND, KANSAS  
PHONE 5057

Badger Drillers, Inc.  
Center of NW NW of Sec. 25-1S-38W  
Cheyenne County, Kansas

15-023-00010-00-00

Schrader No. 1

<u>From</u>	<u>TO</u>	<u>Formation</u>	<u>Remarks</u>
0	235	Surface Sand & Shale	Ran 16 jts of 8-5/8" casing, set at 340' with 197 sacks cement
235	320	Shale w/Sand Streak	
320	340	Shale	
340	2380	Shale & Shells	
2380	2585	Shale & Shells w/Lime Streak	
2585	2700	Shale & Shells	
2700	2800	Sand & Shale Streak	
2800	2915	Shale & Shells & Lime	
2915	3015	Shale & Red Bed w/Lime Streaks	
3015	3070	Sand	
3070	3140	Shale, Red Bed & Sand	
3140	3230	Shale & Lime Streaks	
3230	3290	Anhydrite	
3290	3355	Shale & Shells & Lime	
3355	3428	Lime & Shale	
3428	3455	Lime & Chert	
3455	3525	Lime	
3525	3610	Lime & Shale	
3610	3690	Lime	
3690	3760	Lime & Shale	
3760	3935	Lime	
3935	4220	Lime & Shale	
4220	4525	Lime	
4525	4850	Lime & Shale	
4850	4927	Lime & Sand	
4927	4982	Lime & Sandy Shale	
4982	5130	Lime	- TD Dry Hole

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 21 1959  
9-21-59  
CONSERVATION DIVISION  
Wichita, Kansas

I certify the above to be a true and exact copy of the Driller's Log as shown by the Daily Drilling Reports.

BADGER DRILLERS, INC.



Subscribed and sworn to before me  
this 9th day of June, 1959.

*Martha Maher*  
Notary Public

My commission expires June 26, 1960

PLUGGING			
FILE	SEC 25	T 1	R 310
BOOK	PAGE 63	LINE	29