

15-023-00015-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NW

SEC. 26 TWP. 1 RGE. 39 W

Dry Hole Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Judy

Operator Ben Brack Oil Co. Inc. Address 310 Brown Bldg Wichita,

Field _____ County Cheyenne

Total Depth 5141 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 125' circulated with cement- 5 1/2" at 4757' with

150 sax cement behind- Lane Wells plugs to 4570' - Perforated

at 4496' - pipe squeezed with cement at 4155' with 130-127-

and 55 sax cement.

Filled with chat to 4475', set 4 sax cement with dump bailer,

pulled 2300' 5 1/2", filled hole with mud to 124', set rock and

20 sax cement, mud to 30', set rock and 10 sax cement to 0'.

STATE CORPORATION COMMISSION

FEB 11 1953

CONSERVATION DIVISION
Wichita, Kansas

Edmond Tully
District Conservation Agent

Date 2-7-53

2-11-53

PLUGGING
FILE SEC 26 TWP 1 RGE 39 W
BOOK PAGE 78 LINE 36