

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.--82-3-117

15-023-20072-00-01

API NUMBER 15-023-20,072A

LEASE NAME Ochsner

WELL NUMBER 1

2970 Ft. from S Section Line

4060 Ft. from E Section Line

SEC. 30 TWP. 1S RGE. 41 ~~XXXX~~(W)

COUNTY Cheyenne

Date Well Completed 12-7-87

Plugging Commenced 12-7-87

Plugging Completed 12-7-87

LEASE OPERATOR Gould Oil, Inc.

ADDRESS 411 N. Webb Rd. Wichita, KS 67206

PHONE#(316) 682-5523 OPERATORS LICENSE NO. 5298

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, KS Carl Goodrow, State Plugger

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped mud to 3630', 1st plug from 3630' to 3530' w/25 sx; pumped mud to 2750'; 2nd plug from 2750' to 2350' w/100 sx; pumped mud to 250'; 3rd plug from 250' to 90' w/40 sx; pumped mud to 40', solid bridge at 40'; 4th plug from 40' to surface w/10 sx; 15 sx in rathole and 10 sx in mousehole. All cement 60/40 posmix, 6% gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc.

License No. 5422

Address 801 Union Center Wichita, KS 67202

STATE OF Kansas

COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 31st day of December, 19 87

Janet A. Stuck  
Notary Public

Commission Expires: 12-29-90

