

6 070177

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 023-20, 217-00-20  
NW 1/4 SEC. 35, T. 1 S, R. 40  
1000 feet from N section line  
1000 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6829  
Operator: SOWLE EXPLORATION  
Name & Address: BOX 171  
PHILLIPSBURG, Mo.  
67661

Lease Name FIEBLER Well # 1  
County CHEYENNE  
Well Total Depth 5190 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 250 feet 8 5/8

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ABERCROMBIE DRILLING, INC. License Number 5422  
Address 801 UNION CENTER, WICHITA, Mo. 67202

Company to plug at: Hour: 10:00 PM Day: 13th Month: JUNE Year: 19 84

Plugging proposal received from W. W. TOWNS.

(company name) ABERCROMBIE DRILLING, INC. (phone) 316-262-1841  
were: 8 5/8" - 250 SK 50/50 Pozmix GEL - CA-CL (By SUN CMT.)  
ORDERED 205 SK 50/50 Pozmix GEL - CA-CL - 1 SK 710 CELE AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS  
NO ARBUCKLE (MISS WELL) ELV. 3367' - ANV. 3342'  
NO CIRCULATION PROBLEMS.

RECEIVED STATE CORPORATION COMMISSION  
Plugging Proposal Received by [Signature] (TECHNICIAN) DOIC

Plugging Operations attended by Agent? All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 1:15 AM Day: 14th Month: JUNE Year: 19 84  
ACTUAL PLUGGING REPORT ORDERED - 205 SK 50/50 Pozmix 6% GEL 3% CA-CL - 1 SK 710 CELE - 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS  
1st PLUG @ 3360 FT #/25 SK CMT., 2nd PLUG @ 2620 FT #/100 SK ENT 1 SK CELE  
3rd PLUG @ 270 FT #/50 SK CMT., 4th PLUG SOLID BRIDGE HULLS - PLUG @ 40 FT #/10 SK ENT.  
10 SK RAY HOLE (CIRCULATE) 10 SK MOUSE HOLE (CIRCULATE)  
(CEMENTED BY SUN CMT.)

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-12-84  
INV. NO. 2427

Signed [Signature] (TECHNICIAN) DOIC  
June 29th 2