

12-7-87

6031016

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 023-20,072 ~~A-00-01~~
100' W of
S/2 S/2 NW, SEC. 30, T 1 S, R 41 W/4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5298
Operator: Gould Oil Inc.
Name & Address: 411 N. Webb Road
Wichita, Ks. 67206

2970 feet from S section line
4060 feet from E section line
Lease Name Ochsner Well # 1
County Cheyenne 177.94
Well Total Depth 5475 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____ X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc. License Number 5422
Address Wichita, Kansas

Company to plug at: Hour: _____ PM Day: 7 Month: Dec Year: 19 87

Plugging proposal received from Bill Craig
(company name) Abercrombie (phone) _____

were: 8 5/8" set at 250 cwc. Circ hole w/no less than 36 vis mud. Spot cement
plugs w/drill pipe. Balance all plugs w/mud. Order 190 sks 60/40 Poz 6% Gel 3% CC
8 5/8" w.p. Halliburton Cement Co.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None _____ X

Operations Completed: Hour: 5:45PM Day: 7 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT Spot D.P. and displace cement plugs at 3300' w/25 sks

2750' w/100 sks & 1 sk Hulls

250' w/40 sks

Push w.p. to Kelly depth w/10 sks; to base of cellar use joint of pipe to circ. to plow
depth 15 sks in r.h. and 10sks in m.h.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1988 1-18-88

Remarks: Elev. 3605' Anhy 3300'.
(If additional description is necessary, use BACK of this form.)

I hereby do not observe this plugging.

INVOICED

DATE 1-20-88

INV. NO. 19595

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow