

6030545

API NUMBER 15-023-20,019 *Wood*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NEVENE SEC. 20, T 1 S, R 40
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7311

Lease Name HERMAN WHITE Well # 1

Operator: SHAKESPEARE OIL CO. INC.
Name & Address: P.O. BOX 670
SALEM, ILLINOIS
62881

County CHEYENNE 155.03
Well Total Depth 4770 PB 1613 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 268'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050
Address CHASE, KANSAS 67524

Company to plug at: Hour: PM Day: 22 Month: 8 Year: 19 85

Plugging proposal received from RONNIE
(company name) KELSO CASING (phone) _____

were: 8 5/8 SET @ 268' CWC. 4 1/2 SET @ 1613' W 150 SX. TOP PERF. @ 1480'
ORDER SAND & Com. CNT. RECOVERED 1000' OF 4 1/2" CASING. ORDER
180 SX. 60/40 PORE GEL 3% GEL. 20 SX. GEL 3 SX. HULLS B.T. TITON CNT. CO.
WEBB WATER TRUCKS.

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:30 PM Day: 22 Month: 8 Year: 19 85

ACTUAL PLUGGING REPORT Dump SAND ON PBTD w/ 4 SX. Com. CNT. ON TOP To 1425'
PULL PIPE - Top Plug. Pump Down 8 5/8 3 SX. HULLS 20 SX. GEL.
180 SX. CNT. MIX. MAX. PSI. 600# CLOSE IN 200# PLUG COMPLETE

STATE CORPORATION COMMISSION
SEP 3 1985
9-3-85
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

(If you observe this plugging.

DATE SEP 10 1985

Signed Carl Goodnow
(TECHNICIAN)

INV. NO. 9962