

4-061213

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-023-20,361-0000
NE NE SW /4 SEC. 33, 01 S, 39 W
2510 feet from S section line
2970 feet from E section line

Operator license# 30425
Operator: DNR Oil & Gas, Inc.
Address: 655 Broadway - #525
Denver, CO 80203

Lease: Stevens Well # 1-33
County: Cheyenne
Well total depth 4800 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 245 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 12:30 P.M. Day: 3 Month: December Year: 1999

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Company Phone: -

Were: Order 165 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 3:30 P.M., Day: 3, Month: December, Year: 1999

Actual plugging report:
1st. Plug at 2425' w/100 sxs cement. Dakota 2127' - 2427'.
2nd. Plug at 300' w/ 40 sxs cement. Surface Pipe 245'.
3rd. Plug at 40' w/10 sxs cement.
Rathole with 15 sxs.

Remarks: Allied Cementing.
Condition of casing in hole): GOOD X BAD___ Anhy. plug: YES___ X NO___
Bottom plug (in place): YES___, CALC___, NO X Dakota plug: YES X, NO___
Plugged through TUBING___, CASING___ Elevation: 2127 GL

I did[] / did not[X] observe the plugging.

INVOICED

DATE 12/21/99
INV. NO. 60980

(agent)
RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

DEC 14 1999
12-14-99
CONSERVATION DIVISION
WICHITA, KS

R