

4-031835

6-19

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-023-01,001-00-00  
OWWO  
C SE NE /4 SEC. 33, 01 S, 39 W  
1980 feet from S section line  
660 feet from E section line

Operator license# 5030

Lease Gorthy well # 1-33

Operator: Vess Oil Corporation

County Cheyenne

Address: 8100 E. 22nd. Street  
N. Building #300  
Wichita, Kansas 67226

Well total depth 4990 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 200 feet

162.17

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 19 Month: June Year: 93

Plugging proposal received from: Ed McKenna

Company: Murfin Drilling Company Phone: \_\_\_\_\_

Were: Order 200 sx. 60/40 pozmix - 6% gel. - 3% c.c. - 8 5/8" W.P.  
Halliburton.  
Condition hole before plugging.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 4:00P.M., Day: 19, Month: June, Year: 93

Actual plugging report: Spot & displace plugs with drill pipe.  
1st. plug with 25 sx. @ 3175'.  
2nd. plug with 100 sx. @ 2400' with hulls.  
3rd. plug with 40 sx. @ 250'.  
4th. plug with 10 sx. @ 40'.  
Circulate 15 sx. in rathole.  
Circulate 10 sx. in mousehole.

Remarks: Anhy. 3165' - 3200'.  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES   
Bottom plug(in place): YES  CALC  NO  Dakota plug: YES  NO   
Plugged through TUBING  CASING  Elevation: 3204 GL

I did not  observe the plugging.

**INVOICED**

DATE AUG 03 1993

INV. NO. 38230

6-19 SEP 15 1993

Carl Goodrow  
PK (agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG - 2 1993  
8-2-93  
Form CP-2/3