

6040457

API NUMBER 15-147-30192-00-00⁰² R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C7E-SE, SEC. 22, T. 1 S, R. 18 W
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9058
Operator: Twin Eagle Pet.
Name & Address: 2431 E. 61 St.
Tulsa, Okla. 74136

Lease Name Kent Well # 1 SWD
County Phillips 116.77
Well Total Depth 3593 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 200 w/175

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Conts. License Number _____
Address Russell, Ks.

Company to plug at: Hour: 3:00 PM, Day: 25 Month: 9 Year: 19 85

Plugging proposal received from Steve Bandy
(company name) Twin Eagle Pet. (phone) _____

were: 4 1/2" @ 3592 w/150 Perf - 3350 - 3500'
Sq. @ 1700' w/100 sx Hole in cas. @ 1179'

Ordered 300 sx 60/40 pop 10% gel, 3% cc w/1/4" floreal
30 sx gel, 6 sx hulls.

Plugging Proposal Received by Dennis J. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 PM, Day: 25 Month: 9 Year: 19 85

ACTUAL PLUGGING REPORT

Pumped in 4 1/2" cas. -> 50 sx cement w/hulls, -> 10 sx gel
w/hulls, -> 125 sx cement w/hulls

MAX 600# Shut-in 200#

Pumped in 8 5/8" cas -> 75 sx cement w/hulls -> 10 sx gel
w/hulls, -> 50 sx cement

MAX 400# Shut-in 150#

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE DEC 13 1985
INV. NO. 11480

RECEIVED
NOV 8 1985
11-08-85
CONSERVATION DIVISION
Wichita, Kansas

Signed Dennis J. Hamel
(TECHNICIAN)
FORM CP-2/3
Rev. 01-84
#7-85
mas

JAN 15 1986