

6 010727

X 10-4 D-18,035
15-147-00419-00-01
API NUMBER 15- 12/24/1959

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE, SEC. 30, T 1 S, R 18 W&E
feet from S section line
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Schluntz Well # 4 SWD

Operator: Graham Michaelis corp

County 117.48 Phillips.

Name & Address P.O. Box 232

Well Total Depth 3615 PBD 1468 feet

Russell, Ks. 67665

Conductor Pipe: Size feet

RECEIVED STATE CORPORATION COMMISSION

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well Gas Well Input Well SWD Well xx D&A

Other well as hereinafter indicated

NOV 8 1990
11-08-90

Plugging Contractor Graham Michaelis License Number 5134

Address Same

Company to plug at: Hour: Day: 4 Month: Oct Year: 19 90

Plugging proposal received from Chance Fulls

(company name) Kelso Casing Pulling Co. (phone)

were: Order 50 sks common cement and 200 sks 65/35 poz 8% gel 1/4 lb f.c. per
sk. cement. PBD 1468 -4 1/2 casing at 3614 perf - 1429 - 64. Sq at 793- 878 and
868-1264. w/440 sks cement.

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 11:00AM Day: 4 Month: Oct Year: 19 90

ACTUAL PLUGGING REPORT Ran wireline to t.d. Pumped down casing 8 bbls water /

Rate O.K. perf open. Pumped down casing 50 sks common cement and 110 sks 65/35 poz 8% gel
Max pressure 1000 lb. Closed w/800 lbs. Holding. Tied onto 8 5/8 locked up solid.

checked 10.11.90 com. down 10'

Remarks: Allied Cement Co. bill
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have observed this plugging.

DATE 11-13-90

Signed Dale Balthazor (TECHNICIAN)

INV. NO. 29951