

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-091-21,012 - 00-00
SE,NE Sec/Twp/Rge 6-T13S-R24E
2973 feet from south section line
189 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: KCC State of Kansas Fee Fund
Name & 1500 W. 7th
Address Chanute, KS 66720

Lease/Well# Downey #2
County Johnson
Well Total Depth Approx 660 feet
Production Pipe: 4 1/2 Size Feet 656
Surface Casing: 8 1/2 Size Feet 20

AB oil well _____ Gas Well XXX SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Glaze Drilling Lic. # 5885

Address: 22139 S. Victory RD, Spring Hill, KS 66083-9805

Company to plug at: Hour: 10:00 Day: 23 Month: 4 2004

Plugging proposal received from: District III Staff

Company Name: Kansas Corporation Commission Phone: 620-432-2300

Were: Contractor to pump fluid down 4 1/2 until gas is killed and run string of 1" to TD and circulate cement to surface.

Plugging Proposal Received by: Troy A. Russell

TECHNICIAN
None

Plugging attended by Agent: All XXX Part _____

Operations Completed: Hour: _____ Day: 23 Month: 4 2004

Actual Plugging Report: Contractor was able to pump approximately 120 barrels of fluid down 4 1/2 and successfully stop gas flow and run 1" pipe to approximately 625' and circulate 58 sacks of cement to surface.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 17 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks: _____
(If additional description is necessary, use BACK of this form.)

did did/did not observe this plugging.

Signed: Troy A. Russell
TECHNICIAN



RECEIVED
JUN 04 2004
KCC WICHITA

