

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-091-21,011 -00-00  
SE,NE Sec/Twp/Rge 6-T13S-R24E  
2780 feet from south section line  
219 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: KCC State of Kansas Fee Fund  
Name & 1500 W. 7th  
Address Chanute, KS 66720

Lease/Well# Downey #1  
County Johnson  
Well Total Depth Approx 660 feet  
Production Pipe: 4 1/2 Size Feet 656  
Surface Casing: 8 1/2 Size Feet 20

AB oil well \_\_\_\_\_ Gas Well XXX SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Glaze Drilling Lic. # 5885

Address: 22139 S. Victory RD, Spring Hill, KS 66083-9805

Company to plug at: Hour: 12:00 Day: \_\_\_\_\_ Month: 4 2004

Plugging proposal received from: District III Staff

Company Name: Kansas Corporation Commission Phone: 620-432-2300

Were: Contractor to pump fluid down 4 1/2 until gas is killed and run string of 1" to TD and circulate cement to surface.

Plugging Proposal Received by: Troy A. Russell

TECHNICIAN  
None

Plugging attended by Agent: All XXX Part \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 22 Month: 4 2004

Actual Plugging Report: Contractor was able to pump approximately 120 barrels of fluid down 4 1/2 and successfully stop gas flow and run 1" pipe to approximately 650' and circulate 71 sacks of cement to surface.

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 17 2004

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
WICHITA, KS

I did did/did not observe this plugging.

Signed: Troy A. Russell  
TECHNICIAN

RECEIVED  
JUN 04 2004  
KCC WICHITA

*mu*